

Ten years of the decommissioning of Fukushima Daiichi NPS



福島第一廃炉

10年の歩み

The accident occurred on March 11, 2011

Google Mapより
スクリーンショット

March 11, 2011
Earthquake occurred at 14:46
Tsunami hit at about 15:37

Unit 6
Unit 5
Unit 1
Unit 2
Unit 3
Unit 4

Unit 1	Meltdown
Unit 2	Meltdown
Unit 3	Meltdown
Unit 4	Rooftop wrecked
Unit 5	Paused
Unit 6	Paused

Google

What happened in the reactor?

Tsunami attacked
Power source lost



Damaged the sheds of Units 1,3
and 4 by hydrogen explosions

Spent fuel pool

Emitted radionuclide
by dry vent/wet vent

Leaked radionuclide from
the containment vessel


Generated hydrogen/
Evaporated radionuclide

Melted and collapsed fuel assembly

Dropped molten core down

Primary Containment
vessel (PCV)

Reactor
Pressure vessel



What is the purpose of decommissioning?

Decommissioning is an activity to protect people and the environment from the risks posed by radioactive materials while promoting the dismantling of power plant facilities.

The goal of decommissioning is to reduce the risk to a low enough level.

High-risk conditions

Controlled and stable...
but still uncertain state



Certain risks remain



Ensuring safety
with proactive
management

After
decommissioning

Low-risk conditions

Safe even if left unattended
Everyone can feel secure



The risks are
infinitely low



The site can be
used for other
purposes

Major risk sources

1 Spent fuel removal

Remove and store safely

2 Fuel debris retrieval

Remove and store safely


3 Contaminated water management

Purify, reduce generation and reduce the amount of remaining






4 Solid waste

Once in storage, stabilize, reduce volume and generation, and analyze properties

5 Various other contaminants, etc.



Long-term decommissioning plan (The government's policy)

Since March 11, 2011	December 2011	November 2013	October 2021	Within 2031
Early period	Phase 1	Phase 2	Phase 3	Fulfilment
<ul style="list-style-type: none"> • Cold shutdown • Significantly reducing the release of radioactive materials 	<ul style="list-style-type: none"> • Before the start of spent fuel removal from the first implementing unit 	<ul style="list-style-type: none"> • Before the start of fuel debris retrieval in the first implementing unit 	<ul style="list-style-type: none"> • From the end of Phase 2 through the end of decommissioning (Target period will be 30 to 40 years after Step 2) 	<ul style="list-style-type: none"> • From the end of Phase 2 through the end of decommissioning (Target period will be 30 to 40 years after Step 2) 
			Phase 3—①	Phase 3—②

- PCV internal investigation
- Examining fuel debris retrieval method
- Stagnant water treatment in the buildings
- Spent fuel removal from Unit 3 and 4
- Preparing for spent fuel removal from Units 1 and 2




Spent fuel removal from Unit 3|TEPCO




The underwater ROV for Unit 3 internal inspection| TEPCO

- Spent fuel removal from Units 1 to 6 completed
- Trial retrieval of fuel debris gets started
- Gradual expansion of fuel debris retrieval
- Minimize contaminated water generation
- Proceed with waste storage

Spent fuel removal




Retrieval of fuel debris




Road to decommissioning

Decommissioning process of accidental reactors as considered **internationally**




Decommissioning process of accidental reactors at **Fukushima Daiichi**





The danger level of reactors has decreased dramatically over time

Heating value of the reactor




Radioactivity of the reactor




Value for Unit 3

Radiation safety has significantly improved in the last decade

Concentration of Cs-137 in seawater at the south side of the port



Cs-137 emitted from Units 1 to 4 over the past decade




The general public can also visit without protective gear




Site inspection by local residents in February 2020|METI

Monthly average exposure dose for workers




Immediate after the accident in 2011


Unit 1




Unit 2




Unit 3




Unit 4



Unit 5



Unit 6




Unit 1

292

Spent fuel

Fuel debris
Equivalent to
400




Unit 2

587


Spent fuel

Fuel debris
Equivalent to
548




Unit 3

Fuel debris
Equivalent to
548




Unit 4



Unit 5

1374


Spent fuel



Unit 6

1456


Spent fuel



Around 2031


Unit 1

Fuel debris
Equivalent to
400




Unit 2

Fuel debris
Equivalent to
548




Unit 3


Fuel debris
Equivalent to
548




Unit 4



Unit 5



Unit 6



The priority is to ensure safe storage

- Spent fuel removed from accident reactor is securely stored in dry casks (custody facility).
- Large amount of solid radioactive waste has been stored in temporarily storage will be stored in a robust waste storage facility that is being expanded, with efforts to reduce the amount generated in the future and volume of waste.




Developing the systems and mechanisms by fully taking control of the situation

1

To perform decommissioning project in a reliable, prompt and safe manner.


2

To determine exit strategies for long-term decommissioning project.



Collaboration and roles toward decommissioning

Organizational collaboration has been building across the country to ensure safe and steady progress in decommissioning



Learn from the global examples

1979 to 1989

Fuel debris retrieval operation in
Three Mile Island Unit 2 in the US

The case of debris trapped inside the RPV. The operator retrieved remotely and the retrieval completed in 10 years. In the case of Fukushima Daiichi, since fuel debris is leaking out of the RPV, it will be a much larger scale operation. But helpful examples.

Over the past decade, Japan has built strong partnerships with various nations and international organizations.




Making technological decisions and gaining peace of mind still work in progress - ALPS-treated water issue



Insufficient information
Insecurity....
Reputational damages

Environmental Impact



Disseminating information and dialogue with local residents

Sharing knowledge among stakeholders and organizations involved in

decommissioning

Decommissioning and contaminated and treated water management

Study on Specified Nuclear Facility Monitoring and Assessment

Safety Monitoring Council on decommissioning of Nuclear Power Station in Fukushima prefecture



Exchange of opinions with residents and young people at the International Forum on the Decommissioning of the Fukushima Daiichi NPS



Prospects for future decommissioning




Since March 11, 2011	December 2011	November 2013	October 2021	Within 2031
Early period	Phase 1	Phase 2	Phase 3	Fulfilment
			Phase 3—①	Phase 3—②
<ul style="list-style-type: none"> • Cold shutdown • Significantly reducing the release of radioactive materials 	<ul style="list-style-type: none"> • Before the start of spent fuel removal from the first implementing unit 	<ul style="list-style-type: none"> • Before the start of fuel debris retrieval in the first implementing unit 	<ul style="list-style-type: none"> • From the end of Phase 2 through the end of decommissioning (Target period will be 30 to 40 years after Step 2) 	

Safety on nuclear installation	Accident reactors stably maintained Radiation leakage minimized/ensured monitoring Tsunami and earthquake resistance ensured Proceeded with processing of high-risk source Improved radiation safety environment	Strictly continue radiation containment and environmental improvement Dismantle/maintain unnecessary facilities
Contaminated water management	Measures to reduce contaminated water generation implemented Stagnant water in the buildings reduced ALPS-treated water gradually accumulated	Reduce contaminated water generation Reduce stagnant water Planning ALPS-treated water release
Spent fuel	Spent fuel removal from Units 3 and 4 completed Preparation of spent fuel removal from Units 1 and 2 initiated Stored part of spent fuel in dry cask storage	complete spent fuel removal Reactor internal inspection
Fuel debris	Inside of the accident reactors inspected/ internal conditions presumed Developed fuel debris retrieval equipment/ preparation of trial retrieval	Small scale fuel debris retrieval in Unit 2 Eliminate outdoor storage of rubbles Expanding scale of fuel debris retrieval in Units 1 to 3
Radioactive waste	Waste storage facility expanded /volume reduction operation started Condition of waste in temporary storage improved Radioactive waste characterizing Radioactive waste analytical facility constructed	Store waste/reduce volume/stabilize Analyze waste and debris in analytical facilities Carefully consider the long-term exit strategy (decommissioning plan) in line with the status confirmation and progress of retrieval method.

Future of reconstruction progressing together with decommissioning

2011 ————— 2021 —————> 2050

2012 2013 2014 2015 2016 2017 2018 2019 2020 2021





Thank you